BRUHAT BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Executive Engineeer
Dasarahalli Project Division
B.B.M.P. Bangalore - 73

ITEM - WAR SCHEDULE - B

Name of Work:Developmental works for providing drinking water facility in Shettihalli Ward No.12.

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	3.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight and Forty Six Paise Only
2		Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) P. 46 / I. 9.1 PRED SR 2012-13			
2a	150.00	0 to 50 m	Rmtr	315.18	Rupees Three Hundred Fifteen and Eighteen Paise Only
2b	150.00	50 to 100 m	Rmtr	412.00	Rupees Four Hundred Twelve Only
2c	150.00	100 to 150 m	Rmtr	458.35	Rupees Four Hundred Fifty Eight and Thirty Five Paise Only
2d	150.00	150 to 200 m	Rmtr	484.10	Rupees Four Hundred Eighty Four and Ten Paise Only
2e	150.00	200 to 250 m	Rmtr	560.32	Rupees Five Hundred Sixty and Thirty Two Paise Only
2f	150.00	250 to 300 m	Rmtr	600.49	Rupees Six Hundred and Forty Nine Paise Only
2g	150.00	300 to 350 m	Rmtr	640.66	Rupees Six Hundred Forty and Sixty Six Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
RRUK, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
3	210 180.00	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1364.75	Rupees One Thousand Three Hundred Sixty Four and Seventy Five Paise Only
4	54.00	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	754.47	Rupees Seven Hundred Fifty Four and Forty Seven Paise Only
5	3.00	Providing and fixing 160mm Borewell Cap	Each	100.00	Rupees One Hundred Only
6	3.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps	No	60400.00	Rupees Sixty Thousand Four Hundred Only
7	846 780.00	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark	Rmtr	375.00	Rupees Three Hundred Seventy Five Only
8	138 260.00	Heavy Duty Collar 50 mm dia	Each	130.00	Rupees One Hundred Thirty Only

EXECUTIVE ENGINEER-4
KRIDL / BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
9	1692 1040.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of **GROUP-A. P. No. 12 / I No. 2.10.4(1) 3C x 6 Sqm mm**	Mtr	188.70	Rupees One Hundred Eighty Eight and Seventy Paise Only
10	3.00	Erection of pumpset including aligning and balancing with all necessary erection materials and labour including supply and erection of one pair supporting clamps, one borewell cap. Cable clips with bolts, nuts, valves guages etc., involoved in the job (Necessary GI pipe and specials with be supplied by the board at the site free of cost)	No's	3000.00	Rupees Three Thousand Only
11	3.00	Supplying and fixing 20"x20"x2.5" polished wood board made of not less than 15mm thick plank on both sides with planks made out of not more than 2 pieces and fixing the same to the wall using tapered inverted wooden plugs screws etc., **P No. 44 / I No. 6.6.6 KPWD Electrical SR 2014-15**	Each	302.00	Rupees Three Hundred Two Only
12	90.00	Supplying of 1.1 KV LT UG cable having aluminum conductor PVC insulated, extruded inner sheathed, galvanized, steel strip (except 2CX10Sq.mm wire armoured) confirming to IS-3975:1990 (No. of Strip indicated in GTP) & extruded PVC outer sheathed armoured cable with specified IS-1554 Part-1:1988 & confirming to GTP of GROUP-A **P No. 55/ I No. 7.4.4 4 core 16 Sqmm KPWD Electrical SR 2014-15**	Mtr	140.40	Rupees One Hundred Forty and Forty Paise Only
13	90.00	Labour charges for laying of 1.1 KV class UG cable in existing trench GI pipe / stoneware pipe / on wall / on pole as required.In existing trench/duct. **P No. 61 / I No. 7.8.1 6Sqmm to 16 Sqmm) KPWD Electrical SR 2014-15**	Mtr	10.80	Rupees Ten and Eighty Paise Only
14	75.00	Digging of trench of 0.6m deep x 0.50 mtr wide refilling the trench to the required ground level and consolidating etc., complete.(As per Civil SR KSRB I-2, P-7) **P No. 61 / I. No. 7.9.3 KPWD Electrical SR 2014-15**	Mtr	85.00	Rupees Eighty Five Only
15	12.00	Supplying and fixing of class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV **P. No. 62 / I No. 7.12.1 KPWD Electrical SR 2014-15**	Mtr	345.00	Rupees Three Hundred Forty Five Only
16	3.00	Supplying and fixing L.T. cast Iron pot heads suitable for 1.1 KV class UG cable filled with necessary bitumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc., **P. No. 62 / I.No. 7.13.2 KPWD Electrical SR 2014-15**	No's	280.00	Rupees Two Hundred Eighty Only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
17	3.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 122 mm dia, **(P No. 55, I No. 7.1) KPWD Electrical SR 2014-15**	No.	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
18	36.00	Supplying & fixing of Porcelain fuse channel with cut out on existing wooden/panel using necessary nuts, bolts and washers.**P No. 44 / I No. 6.7.2 KPWD Electrical SR 2014-15**	No	180.00	Rupees One Hundred Eighty Only
19	3.00	KSRB 13-7.1-4: Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 **Page No. 90 Item No. 13.55 / PWD SR 2015-16**	No.	1579.40	Rupees One Thousand Five Hundred Seventy Nine and Forty Paise Only
20	3.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. **P. No. 92 / I. No. 13.81.3 PWD SR 2015-16**	No	227.90	Rupees Two Hundred Twenty Seven and Ninety Paise Only
21	12.00	Supplying and fixing 50mm dia GI X nipple with ISI mark with all lead and lift loading unloading and labour charges etc complete	No	80.00	Rupees Eighty Only
22	3.00	Supplying shunt capaitors conforming to IS 2834, 3phase 400/440 volts grade for power factor improvement of rotating machinery, Capacitor in KVAR rating Nos. 2KVAR capacity with all lead and lift =, loading, unloading and labour charges etc complete as per specifications	No	350.00	Rupees Three Hundred Fifty Only
23	3.00	Supplying and fixing miniature circuit breakers on existing MCB distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, energy cross-3 with Short circuit breaking capacity of 10K and complete wiring as required confirming to IEC 60898.	No	1547.00	Rupees One Thousand Five Hundred Forty Seven Only
24	70200 55800.00	Fabricating supplying and mounting MS box made out ... SWG suitable for floor / wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished with 2 coats of red oxide primer paint and finally finished with approved colour enameled metal paint etc., complete	Sq.Cm	0.33	Thirty Three Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
25	3.00	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. **12.5HP to 15 HP Star Delta Starter SERDED Rate**	No's	11000.00	Rupees Eleven Thousand Only
26	360.00	Earthwork excavation for pipeline trenches including deporiting or bank up to a lead of 50 mtrs including shiriry and statting danger lighting and using site rails and boming poles at every 100 mtrs wherever necessary as directed in th following strructure manhole. **Page No. 01/ Item No.1.2.2 / PRED SR 2012-13 Hard Soil**	Cum	193.64	Rupees One Hundred Ninety Three and Sixty Four Paise Only
27	800 600.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., **Page No.15 item No.3.4.2 b PRED SR 2012-13.**	Rmtr	161.71	Rupees One Hundred Sixty One and Seventy One Paise Only
28	360.00	Refilling the basement and pipeline treanches with secleted available earthe for trench excavation including authority condition in layers from thedi including disponsary of the sunplus earth with a heavy 200 mtrs **Page No. 3 / Item No. 1.6 / PRED SR 2012-13**	Cum	62.83	Rupees Sixty Two and Eighty Three Paise Only
29	2000 6000.00	Polyethelene water storage tank of specified capacity and make moulded frame (For 2000 ltr capacity)	Ltr	6.20	Rupees Six and Twenty Paise Only
30	15.00	KSRB13-6.2-1.Providing and fixing in postion brass stop cpck of approved quality 15mm nominal bore including cost of all materials labour and HOM of equipment with all leads complete as per specification	Each	160.00	Rupees One Hundred Sixty Only
31	600 1200.00	KSRB 13-3.1 Providing and fixing in trenches galvanised/mild steel tubes (medium grade)15mm dia nominal bore with all fitting (earth work in trenches to be measured and paid for separately)including coplete as per specification	Mtr	267.00	Rupees Two Hundred Sixty Seven Only
32	30 50.00	KSRB 13.6.3-6 : Providing and fixing in position brass gate valve with C.I wheel of approved quality (screwed end) **50mm** nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	2120.00	Rupees Two Thousand One Hundred Twenty Only

EXECUTIVE ENGINEER-4
RRDE / BBMP DIVISION
BENGALURU-560 010

Signature of the Contractor

Executive Engineer
Project Division
BBMP, Bangalore - 73